

Schedule 1 – Third Party Designed Details

Scotland

Permitted Items

As detailed in SER Guidance Note 12, SER has divided buildings into five risk groups: RG1A, RG1B, RG2A, RG2B and RG3. The third party designed items which will be permitted on Schedule 1 vary depending on the risk group, and are detailed to the right.

Please note: there is no longer an 'other' option for any risk group. There is a separate tutorial regarding the use of Schedule 1 and generation of Form Qs relating to legacy certificates and certificates which are linked to legacy certificates (e.g. additional stage(s) and amendments to warrant).

Risk Group	Permitted Schedule 1 Items
RG1A RG1B	Piling Vibro stone or concrete columns Precast foundation systems Precast concrete floor units Precast concrete stairs Timber roof trusses Steelwork connections Protective barriers Glazing
RG2A RG2B	Piling Vibro stone or concrete columns Precast foundation systems Precast concrete floor units Precast concrete stairs Timber roof trusses Steelwork connections
RG3	None

Item Selection

When generating a certificate, you will be presented with a list of permissible Schedule 1 items depending on the Risk Group selected for the certificate in the General Project Information section.

Schedule 1 - Third party designed details

ACC: SER1-D-00000

Please note - **ALL** items entered on Schedule 1 must also be included on Schedule 2

Please select the items that form part of the structural design covered by this certificate and are subject to detailed design by a specialist contractor which have yet to be completed.

- Piling
- Vibro stone or concrete columns
- Precast foundation systems
- Precast concrete floor units
- Precast concrete stairs
- Timber roof trusses
- Steelwork connections
- Protective barriers
- Glazing

Save and Continue

[◀ Previous Step](#)

Outstanding Tasks

Once you have paid for and entered signature dates for a certificate which contains at least one item under Schedule 1, you will be presented with an outstanding task entitled 'Certificate awaiting Form Q generation'. Please see the tutorial relating to Form Q generation for further details.

Outstanding Tasks

Certificates awaiting confirmation ▶

2

Certificate awaiting Form Q generation ▼

Certificate number	000000
Project reference	Project Reference
Project title	Project Title
Project location	Project Location
Body	SER1-DB-0000 Project Reference
PDF generated on	05/10/2016 (13:28)
Certifier signature date	05/10/2016
Certification Coordinator signature date	05/10/2016
Actions	Complete Form Q